



NEPTUNE

Data Package Specification

Digital mixing system package shall include capability of monitoring inlet, outlet and recirculation temperatures via the building management system or a web-based interface. Additionally, digital system shall provide continuous data logging and digital alarm capabilities. Package shall maintain set temperature in the event of a power loss to the system. Package shall be factory assembled and tested.

Unit supplied with the following:

- **Four Type J Thermocouple**
- **Modbus TCP/IP Protocol**
- **RJ-45 Communication Connection (Cable not included)**
- **Nema 4 ABS box attached with Stainless Steel Mounting Plate with ¼" holes**
- **9 ft. 120 VAC Power Cord**



MANUFACTURING CO., INC.

5330 East 25th Street
Indianapolis, Indiana 46218
Phone (317) 261-1212
Fax (317) 261-1208

Design and specification subject to change without notice.
Please refer to www.temperedwater.com to ensure most current data sheet and other design solutions