



## NEPTUNE

# Security Package Specification

Digital mixing system package shall include capability of monitoring outlet temperature via the building management system. Additionally, shall provide local pump control, local digital adjustment and security via a lock-out security key system. System shall provide alarm capabilities. System shall maintain set temperature even if power is lost to the system. Package shall be factory assembled and tested.

Unit supplied with the following:

- One Type J Thermocouple
- Modbus RTU Protocol
- RJ-45 Communication Connection (Cable not included)
- Nema 4 ABS box attached with Stainless Steel Mounting Plate with ¼" holes
- 9 ft. 120 VAC Power Cord
- Pump switch box for local pump on/off capability



**MANUFACTURING CO., INC.**

5330 East 25th Street  
Indianapolis, Indiana 46218  
Phone (317) 261-1212  
Fax (317) 261-1208

Design and specification subject to change without notice.  
Please refer to [www.temperedwater.com](http://www.temperedwater.com) to ensure most current data sheet and other design solutions